



LOCALITY PLAN
NTS
MELWAYS: 135 C5

SHEET INDEX

| SHT No. | VER | DESCRIPTION |
|---------|-----|--|
| 1 | P2 | DETAIL PLAN, SERVICES SCHEDULE & SHEET INDEX |
| 2 | P2 | NOTES, PAVEMENT DETAILS, TYPICAL SECTIONS |
| 3 | P2 | INTERSECTION DETAILS - SHEET 1 |
| 4 | P2 | CLAMOROSO DRIVE - LONGITUDINAL & CROSS SECTIONS |
| 5 | P2 | VIELO STREET - LONGITUDINAL & CROSS SECTIONS - SHEET 1 |
| 6 | P2 | VIELO STREET - LONGITUDINAL & CROSS SECTIONS - SHEET 2 |
| 7 | P2 | DRAINAGE LONGITUDINAL SECTIONS |
| 8 | P2 | DRAINAGE LONGITUDINAL SECTIONS, PIT SCHEDULE & PIT DETAILS |
| 9 | P2 | SIGNAGE & LINEMARKING PLAN |

SERVICES OFFSETS AND LOCATIONS

| STREET NAME | Rd RESERVE | WATER | | GAS | ELECTRICITY | | FIBRE TO THE HOME | | Bk. of KERB | JOINT TRENCHING | VICCODE STREET CLASSIFICATION |
|-----------------------|------------|--------|--------|--------|-------------|----------|-------------------|-----------|------------------|-----------------|-------------------------------|
| | | DW | NDW | | CABLES | POLES | FTTH CABLES | FTTH PITS | | | |
| CLAMOROSO DRIVE | 16-00 | 2-85 E | 2-35 E | 1-90 E | 2-50 W | 1-00 BOX | 1-85 W | 1-20 E # | 4-35 E 4-05 W | G & W, FTTH & E | STREET - LEVEL 1 |
| VIELO CIRCUIT (NORTH) | 16-00 | 3-20 S | 2-70 S | 2-25 S | 2-35 N | 1-00 BOX | 1-85 N | 1-78 S | 4-05 N 4-35 S | G & W, FTTH & E | STREET - LEVEL 1 |
| VIELO CIRCUIT (SOUTH) | 16-00 | 3-20 N | 2-70 N | 2-25 N | 2-40 S | 1-00 BOX | 1-85 S | 1-78 N | 4-35 N 4-05 S | G & W, FTTH & E | STREET - LEVEL 1 |

WARNING
BEWARE OF UNDERGROUND SERVICES
THE LOCATIONS OF UNDERGROUND SERVICES ARE APPROXIMATE ONLY AND THEIR EXACT POSITION SHOULD BE PROVEN ON SITE. NO GUARANTEE IS GIVEN THAT ALL EXISTING SERVICES ARE SHOWN.

- ATTENTION TO CONTRACTOR**
- IT IS THE CONTRACTORS RESPONSIBILITY TO ENSURE THAT THE DIGITAL PLAN, PROVIDED FOR SETOUT PURPOSES, MATCHES THE TBM COORDINATES SHOWN.
 - Contractor to ensure that the site is pegged and/or set out checked by the licenced surveyor responsible for certifying the Plan of Subdivision prior to underground infrastructure being installed.
 - Where concrete works about a sewer access chamber surround or similar structure, an expansion joint of approved material shall be provided between the two faces.



SYMBOL LEGEND

| | | | | | |
|------------------|------|-------|---------------------|-------|-------|
| Drains | Prop | Exist | Ex/Natural/FS Level | 28.57 | 28.57 |
| Sewer <300 | — | — | FS @ Building Line | 28.57 | 28.57 |
| Sewer >300 | — | — | Top/Toe of Batter | 28.57 | 28.57 |
| Water | — | — | Top Ret. Wall Level | 28.57 | 28.57 |
| House Drain | — | — | 100yr Flood Level | 28.57 | 28.57 |
| Property Inlet | — | — | Fill Prop/Ex | 28.57 | 28.57 |
| Street Sign | — | — | Cut Prop/Ex | 28.57 | 28.57 |
| PSM | — | — | | | |
| Retaining Wall | — | — | | | |
| Conduits 50mm | — | — | | | |
| Conduits 100mm | — | — | | | |
| Ex Gas/Elect/Tel | — | — | | | |

| VER | DATE | REMARKS |
|-----|------|---------|
| | | |
| | | |

breese pitt dixon pty. ltd.
land surveyors
civil engineers

1/19 coto street
hawthorn east, 3123
telephone 8823 2300
fax no. 8823 2310

DELARAY ESTATE
STAGE 18

MELWAY REF. 135-D-4
SURVEY BPD
DESIGN GL
DRAWN GL

MUNICIPALITY
CASEY

REFERENCE
8974 E/18

SCALE AS SHOWN
DATUM AHD
DATE JAN'20
SHEET 1 OF 9 P2