



## GENERAL NOTES

This fill plan shows details of works affecting the natural surface of the land, being fill placed on the land to the extent and depth shown on this plan.

The depth of fill is determined from bulk earthworks performed by Midland Contracting and is confirmed by survey provided by Landform Surveys and is correct at 27th of March 2018.

There is still some further material to be placed at a future date in order to achieve the final design surface levels.

This plan does not show any other fill which may have been placed on the land.

Any grading or spreading to correct minor surface irregularities less than 300mm in depth is not shown.

Depths shown are not recommended foundation depths.

## FILL DEPTHS



6		
5		
4		
3		
2		
1	Original Issue	26/4/2018
0	Draft	-
Ver	Revision Description	Date

Designed	Checked
R. Dawborn	N. Bowe
Apr 2018	Apr 2018
Approved	

Notes/Legend

**TERRACO**  
Civil Engineers  
Project Managers  
Development Consultants

Terraco P/L  
ABN 12 681 695 776  
Corner Jewell Court  
& Rowena Street  
Bendigo Vic 3550  
Ph: 03 5442 5799  
Fax: 03 5441 5506  
E: info@terraco.com.au

Scale (m) H 1:1250 0 12.5 25  
All lengths are in metres  
and all levels are to Australian Height Datum  
(Original Sheet Size is A3)

Drawing file:	LTO Ref:
16123 Fill.dwg	-

Murray River Council - Moama  
Villawood Properties Pty Ltd  
Lakeview Estate - Bulk Earthworks  
Lot Fill Plan - Stages 9-11

Council Ref:	Our Ref:	Version	Sheet
DA 173/11	16123	1	1 of 1