

<b>PLAN OF SUBDIVISION</b>	EDITION 1	<b>PS 819166Y/S3</b>
----------------------------	-----------	----------------------

LOCATION OF LAND

PARISH: WOLLERT  
TOWNSHIP: -  
SECTION: -  
CROWN ALLOTMENT: -  
CROWN PORTION: 16 (PART)  
TITLE REFERENCE: C/T VOL ..... FOL .....

LAST PLAN REFERENCE: LOT S5 ON PS 819166Y/S2

POSTAL ADDRESS: 430 - 440 CRAIGIEBURN ROAD  
(at time of subdivision) WOLLERT 3750

MGA94 CO-ORDINATES: E: 322 990                      ZONE: 55  
(of approx centre of land                      N: 5 836 750  
in plan)

<b>VESTING OF ROADS AND/OR RESERVES</b>	<b>Notations</b>
---	------------------

IDENTIFIER	COUNCIL/BODY/PERSON
ROAD R-3	WHITTLESEA CITY COUNCIL
RESERVE No. 4	WHITTLESEA CITY COUNCIL
RESERVE No. 5	AUSNET ELECTRICITY SERVICES PTY. LTD.

This is a SPEAR plan.

Land being subdivided is enclosed within thick continuous lines.

Lots 1 to 637 and S1 to S5 (all inclusive) have been omitted from this plan.

None of the easements and rights mentioned in sub-section (2) of Section 12 of the Subdivision Act 1988 are implied over any of the land in this plan.

**NOTATIONS**

DEPTH LIMITATION DOES NOT APPLY

**SURVEY:**  
This plan is based on survey

**STAGING:**  
This is a staged subdivision  
Planning Permit No. 716630

This survey has been connected to permanent marks No(s). 38, 21, 40 & 52  
In Proclaimed Survey Area No. -


LOTS ON THIS PLAN MAY BE AFFECTED BY ONE OR MORE OWNERS CORPORATIONS  
For details of Owners Corporation(s) including; Purpose, Responsibility and Entitlement and Liability see Owners Corporation Search Report, Owners Corporation Rules and Owners Corporation Additional Information.



**EASEMENT INFORMATION**


LEGEND: A - Appurtenant Easement    E - Encumbering Easement    R - Encumbering Easement (Road)

Easement Reference	Purpose	Width (Metres)	Origin	Land Benefited/In Favour of
E-1	DRAINAGE	SEE DIAG	PS 803931Y	WHITTLESEA CITY COUNCIL
E-1	SEWERAGE	SEE DIAG	PS 803931Y	YARRA VALLEY WATER CORPORATION
E-2	DRAINAGE	SEE DIAG	THIS PLAN	WHITTLESEA CITY COUNCIL
E-2	SEWERAGE	SEE DIAG	THIS PLAN	YARRA VALLEY WATER CORPORATION
E-3	SEWERAGE	SEE DIAG	THIS PLAN	YARRA VALLEY WATER CORPORATION

RATHDOWNE ESTATE - STAGE 6 (33 LOTS) AREA OF STAGE - 2.261ha


	414 La Trobe Street PO Box 16084 Melbourne Vic 8007 T 61 3 9993 7888 spiire.com.au	SURVEYORS FILE REF: <b>305342SV00</b>  Licensed Surveyor: Mark Oswald Stansfield Version: 3	ORIGINAL SHEET SIZE: A3  SHEET 1 OF 6
---	--	--	--





S6  
SEE SHEET 2

SEE SHEET 4





S6  
SEE SHEET 2

LAKERIDGE DRIVE

LAKERIDGE DRIVE

BRASSWOOD WAY

PREVELI WAY




SEE SHEET 3



414 La Trobe Street  
PO Box 16084  
Melbourne Vic 8007  
T 61 3 9993 7888  
spiire.com.au

SCALE  
1: 750



ORIGINAL SHEET  
SIZE: A3

SHEET 4

Licensed Surveyor: Mark Oswald Stansfield  
Ref: 305342SV00  
Version: 3

**CREATION OF RESTRICTION No. 1**

The following restriction is to be created upon registration of this plan.

Land to Benefit: Lots 638 to 670 (both inclusive)  
Land to be Burdened: Lots 638 to 670 (both inclusive)

For the purpose of description

(i) Primary frontage means

- (A) In the case of a lot where only one boundary of that lot abuts a road, the boundary that abuts the road.
- (B) In the case of a corner lot where two boundaries of a lot abut a road, the boundary with the greater offset on the building envelopes within the Rathdowne Building Design Guidelines.

Description of Restriction:

The registered proprietor or proprietors for the time being of a lot on this plan of subdivision his/her heirs, executors, administrators and transferees shall not at any time on the said lot or any part or parts thereof;

- (i) Build or cause to be built or allow to be built or allow to remain more than one private dwelling (which expression shall include a house, apartment, unit or flat);
- (ii) Build or cause to be built or allow to be built or allow to remain a dwelling or any other improvements, or carry out cause to be carried out or allow to be carried out any building or construction works on the lot prior to 10 years from the date of registration of this plan:
  - (A) Copies of building plans, elevations, roof plan, site plan (incorporating setback from all boundaries, building envelope, existing contour, proposed finished floor levels and site levels, all proposed driveways and paths, details of fences and outbuildings and landscaping) and schedule of external colours and materials ("plans") have been submitted to the Design Assessment Panel, at the address in the Design Guidelines (as amended from time to time) or such other entity as may be nominated by the Design Assessment Panel from time to time;
  - (B) The plans comply with the Rathdowne Building Design Guidelines, a copy of which can be obtained from the Design Assessment Panel, at the address in the Design Guidelines (as amended from time to time);
  - (C) The Design Assessment Panel or such other entity as may be nominated by the Design Assessment Panel from time to time has given its written approval to the plans as being in accordance with the "Rathdowne Building Design Guidelines" prior to the commencement of works;
- (iii) Build or cause to be built or allow to be built or allow to remain a garage;
  - (A) Which contains a garage door or doors of which the garage opening/s occupy more than 40% of the width of the primary frontage unless in the case of dwellings of two or more storeys on lots between 250 square metres and 300 square metres whereby the garage opening must not exceed 30% of the area of the front facade of the dwelling, with the area of the front facade measured from a two dimensional elevation plan excluding any roof area of the dwelling.
- (iv) Build or cause to be built or allow to remain any fencing:
  - (A) Along a front street boundary; and
  - (B) Between the front street boundary and the building line; and
  - (C) Upon a side or rear boundary of a lot except a fence:
    - (a) Which is constructed of timber palings with exposed posts capped across the top of the palings; and
    - (b) Which does not exceed 1.8 metres in height excluding a screen erected to meet the requirements of Part 4 of the Building Regulations 2006 in relation to overlooking
- (v) Use the said lot in any way that is not in accordance with the "Rathdowne Building Design Guidelines"

**CREATION OF RESTRICTION No. 2**

The following restriction is to be created upon registration of this plan.

Land to Benefit: Lots 638 to 670 (both inclusive)  
Land to be Burdened: Lots 638 to 670 (both inclusive)

Description of Restriction:

The registered proprietor or proprietors for the time being of any burdened lot on this Plan shall not:

- (i) Construct a dwelling on a lot presenting sideage adjoining any form of open space unless:
  - (A) The development consists of a double storey dwelling;
  - (B) The development includes passive surveillance features such as large windows and balconies at the first storey level overlooking the adjoining open space; and
  - (C) Any fencing of the front yard adjoining the open space is feature style, with a minimum 25% transparency and has a maximum height of 1.50 metres.
- (iii) Construct a dwelling or commercial building on any lot unless the building incorporates dual plumbing for the use of recycled water in toilet flushing and garden watering.

**CREATION OF RESTRICTION No. 3**

The following restriction is to be created upon registration of this plan for lots greater than 300m<sup>2</sup>.

Land to Benefit: Lots 638 to 670 (both inclusive)  
Land to be Burdened: Lots 638 to 670 (both inclusive)

Description of Restriction:

The registered proprietor or proprietors for the time being of any burdened lot on this Plan shall not:

- (i) Construct the side wall of the first level of any dwelling on a corner lot less than 900 millimetres from the ground level wall that faces a side street.
- (iii) Construct any garage on a lot between 2.20 metres and 5 metres from the title boundary alignment at the front of the lot.
- (iii) Construct any garage other than a single garage where access is proposed from the lot frontage on a lot with a width of a 10 metres or less at the lot frontage.

**CREATION OF RESTRICTION No. 4**

The following restriction is to be created upon registration of this plan for lots less than 300m<sup>2</sup>.

Land to Benefit: Lots 638 to 670 (both inclusive)  
Land to be Burdened: Lots 643 and 644 (both inclusive)

The registered proprietor or proprietors for the time being of any burdened lot on this plan in this restriction as a lot subject to the 'Small Lot Housing Code (Type A)' must not build or permit to be built or remain on the lot any building or structure that has not been constructed in accordance with the 'Small Lot Housing Code (Type A)' unless in accordance with a permit granted to construct a dwelling on the lot. This restriction shall cease after the issue of Certificate of Occupancy for the whole of the dwelling on the lot.